

Job wise labour rates for maintenance works for the year 2022-23- Justification thereof.

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2022-23 (Rs.)
1	3 Straitening of leaned poles:-	4	5	6	7	8	9	10	11	12
	(a) Straitening of 140 Kg 8 mtr long PCC poles (Including pit digging Straitening & back filling with boulders & ramming including cost of boulders)	350	367	3	2	35.50	275	311	62	373
	(b) Straitening of 272 Kg 9.1 mtr long PCC poles (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	505	367	4	2	80	367	447	89	536
	(c) Rail pole / H-Beam / R.S.Joist (175x85 mm) (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	629	367	5	2	97.50	459	556	111	668
	(d) R.S.Joist (125x70 mm) (Including pit digging, Straitening & back filling with boulders & ramming including cost of boulders)	523	377	4	2	94.50	377	472	94	566
	Dismantling of damaged old support completely (For 33 KV & 11 KV lines)									
2	(a) 140 Kg 8 mtr long PCC pole Taking out of V cross arm, top clamp insulators, 4 pin cross arm etc. de-erection of pole & shifting	289	367	2	2	70	184	254	51	304
	(b) 272 Kg 9.1 Mtr long PCC Pole Taking out of V cross arm, top clamp insulators etc., de-erection of pole & shifting	313	367	2	2	90.50	184	274	55	329
	(c) Rail pole / H-Beam / R.S.Joist (175x85 mm) Cutting of pole by gas cutter / Dismantling, taking out of V-cross arm, top clamp insulators etc. shifting & loading in Board's vehicle.	877	367	5	2	304.50	459	763	153	916
	(d) R.S.Joist (125x70 mm) Cutting of pole by gas cutter / Dismantling, taking out of cross arm, 4 pin cross arm and insulators etc. shifting and loading in company's Vehicle	775	377	4	2	305	377	682	136	818
3	Renovation of stay providing stay wire only where stay rod is found intact	158	367	2	1.50	4	138	142	28	170

Handwritten signature and initials

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021- 22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	New stay- Pit digging, grouting, concreting & erection									
	(i) New stay for 33 KV line 20 mm	512	392	4	2	60.50	392	453	91	543
4	(ii) New stay for 11 KV line 16 mm	236	392	1	2	105.50	98	204	41	244
	(a) For urban areas with concreting cement will be provided by the board	248	422	1	2	107.50	106	213	43	256
	(b) For rural areas with stone block	217	422	1	2	81.50	106	187	37	224
	Painting of poles : cleaning of metallic surface by wire brush, 2 coats of red oxide & 1 coat of Aluminium paint on all the steel surfaces, paint will be provided by the board & wire brush will be provided by the contractor.									
5	(a) Rail pole, R.S.Joist, H-Beam	242	422	1	2	102.50	106	208	42	250
	(b) V-cross arm & Top clamp 11 KV & 33 KV	182	422	2	1.50	3.50	158	162	32	194
	(c) LT 3 / 4 / 5 Pin cross arm each	67	422	1	1	6.50	53	59	12	71
	(d) DC channel (8'5".4', SPC) for 33 KV & 11 KV	138	422	2	1	16	106	122	24	146
	Numbering of poles:- Preparing base by black paint at the height of 05 feet from ground level for writing pole number with white paint of size 4" including cost of paint and labour charges.	65	422	1	1	4.50	53	57	11	69
6	(a)									
	(b) Obtaining G.I.S. co-ordinates per pole (latitude & longitude) for works to be executed in R-APDRP town areas.	5.00 per location/pole					5.00 per location/pole	5.00 per location/pole		5.00 per location/pole
	Painting of X-mer:- Cleaning of X-mer body with water, brush, detergent & providing paint labour charges only, paint shall be provided by board									
7	(a) 25 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	311	392	2	2	76.50	196	273	55	327
	(b) 50/63 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	373	392	2	2	128	196	324	65	389
	(c) 100 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	436	392	2	2	180	196	376	75	451
	(d) 200 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	448	392	2	2	190.50	196	387	77	464
	(e) 315 KVA X-mer: 2 coats of Red oxide & one coat of Gray paint	473	392	2	2	211	196	407	81	488
	(f) 500 KVA X-mer 2 coats of Red oxide & one coat of Gray paint	596	392	2	2	314	196	510	102	612

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021- 22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	Straitening of tilted V cross arm & top clamps provided with back clamps									
8	(a) 33 KV V-cross arm (Where replacement of V-cross arm not required :- Material supplied by board	138	392	2	1.25	0.50	123	123	25	148
	(b) 11 KV V-cross arm (Where replacement of V-cross arm not required :- Material supplied by board	57	392	1	1	2	49	51	10	61
	(c) 33 KV Top clamp (Where replacement of V cross arm not required :- Material supplied by board	36	392	1	0.65	0	32	32	6	38
	(d) 11 KV Top clamp (Where replacement of V cross arm not required :- Material supplied by board	36	392	1	0.65	0	32	32	6	38
9	Replacement of bent V cross arm :- Taking out of bent cross arm & replacement by new one along with taking out of 02 No. insulators, binding opening & again providing the same.									
	(a) 33 KV	151	367	1	2	40.50	92	132	26	159
	(b) 11 KV	107	367	1	1	47	46	89	18	107
10	Replacement of Top clamps:- Taking out of damaged top clamp, 01 No. insulator opening, binding & again providing New top clamp along with fixing of insulator & rewinding									
	(a) 33 KV	84	367	1	1.65	0	76	76	15	91
	(b) 11 KV	41	341	1	0.77	1	33	34	7	41
	Renovation of earthing of poles for single locations (material shall be supplied by the Board)									
	(a) 33 KV	144	367	1	1	77.50	46	123	25	148
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
11	(b) 11 KV	138	367	1	1	72.50	46	118	24	142
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
	(c) LT line	102	367	1	1	42	46	88	18	105
	Pit digging, putting of earthing coil/ with back filling, connecting earthing coil with steel structure of pole.									
12	Making holes on Rails, R.S.Joist, H-Beam by gas kit / Ratchet for earthing / Top clamp fixing etc.	78	367	1	1	22	46	68	14	81
13	Replacement of Damaged Disc insulator taking out of line conductor, replacement of Disc & again fixing the line conductor & renovation of jumper using trifer or turn buckle.	290	367	2	2	71.50	184	255	51	306

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021-22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
14	Replacement of Damaged Pin insulator									
	(a) 33 KV	52	367	1	1	1	46	47	9	56
	(b) 11 KV	32	367	1	0.63	0	29	29	6	35
15	Restringing of line conductor for 33/11 KV line work includes opening of binding of conductors from the insulators taking out of conductors from the Disc & retensioning the conductor & rewinding of it as the insulator (ACSR / AAAC Conductor) rates are taken per Km per phase									
	(a) Raccoon & Dog conductor per Km / conductor	1413	367	7	3	282	963	1245	249	1494
	(b) Rabbit conductor	984	367	6	2	308.50	551	859	172	1031
	(c) Weasel	780	367	4	2	309	367	676	135	811
	(d) Squirrel	575	367	4	1	309	184	493	99	591
16	Replacement / AUGUMENTATION of line conductor (for 33/11 KV) The work includes opening the binding of insulators of the sections, dismantling old conductors & coiling the conductor properly, laying out New conductor & tensioning it on the line with proper sag & binding of the conductor with insulator (ACSR & AAC) 1.5 times of standard rate.									
	(a) Raccoon & Dog conductor per Km / conductor	4130	367	10	7	458	3211	3669	734	4403
	(b) Rabbit conductor	3310	367	10	6	200.50	2753	2953	591	3544
	(c) Weasel	2537	367	10	4	409	1835	2244	449	2693
	(d) Squirrel	2351	367	10	4	254	1835	2089	418	2507
17	Replacement of fixed & moving contacts of AB awitch with (Adjustment of complete unit greasing and renovation of jumper wire each location)									
	(a) 33 KV	328	367	2	2	103	184	287	57	344
	(b) 11 KV	215	367	2	2	9	184	193	39	231
18	Providing stay insulator to LT lines, cutting of stay wire binding of stay insulators & erection & tightening of stay	119	367	1	2	14	92	106	21	127

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021-22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
19	<p>a. Re-stringing of line conductor in LT, removing of service lines, diamond guarding and binding, retensioning of the conductor and reproviding diamond guarding, service jumpering etc. (considering 08 services per span)</p> <p>b. Re-stringing of line conductor in LT, diamond guarding and binding, jumpering of the conductor and reproviding diamond guarding, service jumpering etc. (considering 08 services per span)</p> <p>Providing extension piece to maintain safe clearance as per IE rules (each location)</p>	350	367	2	2	121.50	184	305	61	366
20	<p>a. 33 KV each location</p> <p>b. 11 KV each location</p> <p>Straitening of DP</p> <p>Pit digging 50%, loosening of stay straightening of DP tightening of stay and back filling of pit</p>	271	367	2	2	55.50	184	239	48	287
21	<p>a. 33 KV</p> <p>1 272 Kg PCC pole</p> <p>2 Rail / H-Beam / R.S.Joist</p> <p>b. 11 KV</p> <p>1 140 Kg PCC pole</p> <p>2 Rail / H-Beam / R.S.Joist</p> <p>Renovation of Carpet guarding</p>	352	367	2	2	123	184	307	61	368
22	<p>a. 33 KV</p> <p>b. 11 KV</p> <p>c. LT line</p> <p>Service line renovation (only labour charges)</p>	278	367	2	2	61.50	184	245	49	294
23	<p>a. Single phase</p> <p>b. Three phase</p> <p>LT jumper renovation</p>	329	367	2	2	103.50	184	287	57	344
24		836	367	4	2	355.50	367	723	145	867
		1089	367	5	3	268.50	688	957	191	1148
		611	367	4	2	168	367	535	107	642
		780	367	4	2	309	367	676	135	811
		1607	367	8	3	316.50	1101	1418	284	1701
		876	367	5	2	304	459	763	153	915
		362	367	2	2	131	184	315	63	377
		164	367	2	1.60	0	147	147	29	176
		272	367	2	2	56.50	184	240	48	288
		33	367	1	0.65	0	30	30	6	36

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021- 22 (Rs.)	
1	2	3	4	5	6	7	8	9	10	11	12
	Tree cutting and trimming of tree branches :-										
25	a.	LT line	97	367	1	1.77	0	81	81	16	97
	b.	11 KV Line	110	367	1	2	0	92	92	18	110
	c.	33 KV Line	185	367	2	1.50	17	138	155	31	186
26		Replacement of Distribution box	410	367	2	2	159	184	343	69	411
		Replacement of cable (3.5 core) Replacement will be with lugs materials will be provided by the Company									
	a.	300 sq. mm.	636	367	4	2	164	367	531	106	637
	b.	150 sq. mm.	574	367	4	2	112	367	479	96	575
	c.	70 sq. mm.	437	367	3	2	90	275	365	73	438
27		Replacement of DO fuse unit (each)									
	a.	33 KV	176	367	2	1.50	19	138	157	31	188
	b.	11 KV	117	367	2	1	12	92	104	21	125
28		Replacement of phase main switch	235	367	2	2	25.50	184	209	42	251
		Replacement of porcelain kit-kat	77	367	1	1.50	0	69	69	14	83
30		Replacement of lightning arrester as per schedule									
	a.	33 KV	136	367	1	2	28	92	120	24	144
	b.	11 KV	65	367	1	1.27	0	58	58	12	70
31		Replacement of Silica Jel	35	367	1	0.68	0	31	31	6	37
		Renovations of Jumpers of DT S/s. alongwith lugging (material will be supply by the Company)	309	367	2	2	87	184	271	54	325
33		Commissioning of meter at DT (installation of meter box, meter, cabling, commissioning complete by skilled labour)	882	367	5	2	309	459	768	154	921

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021- 22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
proposed Additional Job work already incorporated in 2022-23										
	Shifting of location of meter from inside to outside consumer premises labour charges									
1	a Single phase connection	242	367	2	2	31	184	215	43	257
	b Three phase connection	380	367	3	2	61	275	336	67	404
2	Replacement of old meter box by installation of new pillar Box in complex including fixing & laying of cables and shifting of connection only labour charges	4859	367	10	8	639	3670	4309	862	5171
3	Indexing of consumer premises, survey, meter card fixing, writing of S/C no., line diagram preparation, from DT to consumer premises each DT wise	38	367	1	0.74	0	34	34	7	41
4	DT meter installation including CT / meter box and meter installation (only labour charges)	811	367	4	2	335	367	702	140	842
5	Laying of HT ABC cable (labour charges) 33 KV	9243	367	15	12	30	8258	8288	1658	9945
6	Laying of HT ABC cable (labour charges) 11 KV	6350	367	15	8	177	5505	5682	1136	6818
7	Fixing of LT junction box on the pole for providing LT connection	205	367	2	2	0	184	184	37	220
8	Providing Earthing of Distribution S/s including pit digging laying and connecting wire to support, X-mer etc. Back filling of pit by Black Cotton soil (only labour charges) per pitwise	811	367	4	2	335	367	702	140	842
proposed Additional Job work already incorporated in proposal 2022-23										
1	Cleaning of 33/11 KV S/s. Yard (approx. 75% area of S/s.) including removal of grasses, tree plants removal dusting etc.	4130.40	367	12	6	373	3303	3676	735	4411
2	Renovation of yard levelling and metalling with cleaning, scraning labour charges	2587.20	367	8	6	110	2202	2312	462	2774
	ABC cable end joint replacement and fixing		367							
3	a Per phase	836	367	4	2	355.50	367	723	145	867
	b Straight joint	1382	367	6	4	129	1101	1230	246	1476
	c. LT end joint per phase	108	367	1	2	5	92	97	19	116
	d LT straight joint per phase	141	367	1	2	32.50	92	124	25	149

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled / Skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021-22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
	UG XLPE Cable end joint replacement and fixing									
4	a HT end joint per phase	1829	462	7	5	32	2021	2053	411	2464
	b Straight joint per phase	2250	462	7	6	85	2426	2511	502	3013
	X-mer maintenance work									
	i Replacement of stud (HT/LT) labour charges only material provided by CSPDCL									
	a 63 KVA 11/0.4 KV X-mer	255	392	2	2	42	196	238	48	286
	b 100 KVA 11/0.4 KV X-mer	320.10	392	3	2	11	294	305	61	366
	c 200 KVA 11/0.4 KV X-mer	345.30	392	3	2	32	294	326	65	391
	d 315 KVA 11/0.4 KV X-mer	371	392	3	2	53	294	347	69	416
	e 500 KVA 11/0.4 KV X-mer	395.70	392	3	2	74	294	368	74	442
5	ii Job work for renovation of complete Maintenance of D X-mer with replacement of Oil seal, burnt stud HT & LT, filtration of X-mer Oil, opening and tightening of core and winding and painting including minor repairing such as replacement of burnt stud change of LT/HT bushing etc.									
	a 63 KVA 11/0.4 KV X-mer	3964.80	392	6	8	1258	2352	3610	722	4332
	b 100 KVA 11/0.4 KV X-mer	4786.20	392	8	8	1260.50	3136	4397	879	5276
	c. 200 KVA 11/0.4 KV X-mer	5947.20	392	8	9	1887	3528	5415	1083	6498
	d 315 KVA 11/0.4 KV X-mer	7108.20	392	8	10	2513.50	3920	6434	1287	7720
	e 500 KVA 11/0.4 KV X-mer	8430	392	8	12	2933	4704	7637	1527	9164
	Distribution box door repairing / providing new door and its replacement against damaged / missing (labour charges with material)									
6	A. Upto 100 KVA Distribution box	1520	422							1520
	B. Above 100 to 200 KVA Distribution box	1646	422							1646
	C. 300 to 500 KVA Distribution box	1774	422							1774

S. No.	Particulars	Rate as per SOR for 2020-21	Wages fixed by Collector for Unskilled / Semi-skilled Labour for 8 hour working per day (Rs.)	No. of Labour Required	Working Hour / per Labour	Cost of Material Involved (Rs.)	Net Amount (Rs.)	Total (Rs.)	Over Head charges @ 20%	Total rate for 2021-22 (Rs.)
1	3	4	5	6	7	8	9	10	11	12
7	Providing BPL Connection with Material including labour charges (Meter board 10"x12" 01 no. GI Wire 16 swg, Earthing terminal 01 no. 1/2"-04 no. nuts and bolts with washer for fixing of board, Plano switch 5 Amp., 01 no. bulb Holder, 16 Amp. cut-out, 02 no. Screw for fixing in meter and cut-out etc., 1.5 mm. up to maximum 30 meter.) (Remark :- The cost service wire to deducted @ Rs. 5.00 per meter on the basis of actual length of wire reduced by 30 meter length).	411	422							411
proposed Additional essential work already incorporated in SOR 2022-23										
1	Replacement of XLPE cable U/G and removing of faulty cable per span i.e. 100 mtr. Span (per span)	10863								11623
2	Replacement of AB cable and removing of faulty cable per span i.e. 100 mtr. Span (per span)	604								646
3	Replacement of XLPE U/G cable end terminal kit (per phase)	2414								2583
4	Replacement of straight joint for XLPE U/G cable (per phase)	3621								3874
5	a Replacement of AB cable end joint per phase including material of good quality	1207								1291
	b Replacement of AB cable end joint per phase (only labour charges)	604								646
6	a Replacement of AB cable straight joint including material of good quality (per phase).	1811								1938
	b Replacement of AB cable straight joint (only labour charges)	604								646
Note The labour engaged should be Minimum qualification at least 12 th passed having knowledge / working of computer preferable ITI Passed										
Remark:- Revision of above proposal is on the basis of following points										
1	The above rate has been revised according to wages declared by Labour Commissioner under Minimum Wage Act-1948 w.e.f 01.10.2021 to 31-03-2022 for unskilled labour Rs. 367.00 per day, semi skilled labour Rs. 391.00 per day and skilled labour Rs. 422.00 per day as per circular of Assistant Labour Commissioner Raipur District Raipur.									
2	Labour contractor have to bear the responsibility of the All labour Rules applicable to him i.e. EPF deduction / payment of income tax / GST, workmen compensation etc.									
3	Contractor have to deposit the addle. Money as provision in भवन एवं अन्य संनिर्माण कर्मकार (नियोजन एवं सेवा शर्तों को विनियम) अधिनियम 1996 की धारा 18(1) एवं 18(3) सह यदित नियम 251 के अनुसार असंगत क्षेत्र के कर्मकारों के हित के लिए नियोजको से निर्माण लागत का एक प्रतिशत की दर से उपकर मंडल को देय होगा जो कर्मकारों के हित के लिए विभिन्न कल्याणकारी योजनाओं में राशि का उपयोग किया जाना है।									

[Handwritten signature]

अनुसूची- 'ख'

अनुसूचित नियोजन भाग-एक के 45 नियोजन

(दिनांक 01.04.2021 से 30.09.2021 तक)

(दिनांक 01.10.2021 से 31.03.2022 तक)

क्र	श्रमिकों का वर्ग	जो न का नाम	न्यूनतम मूल वेतन		परिवर्तनशील मंहगाई भत्ता		कुल वेतन रूपये में		न्यूनतम मूल वेतन		परिवर्तनशील मंहगाई भत्ता		कुल वेतन रूपये में		
			प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह	प्रतिदिन	प्रतिमाह
1	अकुशल	अ	8320.00	320.00	1400.00	53.85	9720.00	373.85 (374)	अ	8320.00	320.00	1480.00	56.92	9800.00	376.92 (377)
		ब	8060.00	310.00	1400.00	53.85	9460.00	363.85 (364)	ब	8060.00	310.00	1480.00	56.92	9540.00	366.92 (367)
		स	7800.00	300.00	1400.00	53.85	9200.00	353.85 (354)	स	7800.00	300.00	1480.00	56.92	9280.00	356.92 (357)
2	अर्द्धकुशल	अ	8970.00	345.00	1400.00	53.85	10370.00	398.85 (399)	अ	8970.00	345.00	1480.00	56.92	10450.00	401.92 (402)
		ब	8710.00	335.00	1400.00	53.85	10110.00	388.85 (389)	ब	8710.00	335.00	1480.00	56.92	10190.00	391.92 (392)
		स	8450.00	325.00	1400.00	53.85	9850.00	378.85 (379)	स	8450.00	325.00	1480.00	56.92	9930.00	381.92 (382)
3	कुशल	अ	9750.00	375.00	1400.00	53.85	11150.00	428.85 (429)	अ	9750.00	375.00	1480.00	56.92	11230.00	431.92 (432)
		ब	9490.00	365.00	1400.00	53.85	10890.00	418.85 (419)	ब	9490.00	365.00	1480.00	56.92	10970.00	421.92 (422)
		स	9230.00	355.00	1400.00	53.85	10630.00	408.85 (409)	स	9230.00	355.00	1480.00	56.92	10710.00	411.92 (412)
4	उच्च कुशल	अ	10530.00	405.00	1400.00	53.85	11930.00	458.85 (459)	अ	10530.00	405.00	1480.00	56.92	12010.00	461.92 (462)
		ब	10270.00	395.00	1400.00	53.85	11670.00	448.85 (449)	ब	10270.00	395.00	1480.00	56.92	11750.00	451.92 (452)
		स	10010.00	385.00	1400.00	53.85	11410.00	438.85 (439)	स	10010.00	385.00	1480.00	56.92	11490.00	441.92 (442)

टीप : न्यूनतम वेतन अधिनियम, 1948 के अन्तर्गत 45 अनुसूचित नियोजनों की सूची परिशिष्ट- 'अ' तथा इस संबंध में स्पष्टीकरण परिशिष्ट- 'ब' में देखें।

(अमृत कुमार खलखो)
श्रमायुक्त एवं सक्षम प्राधिकारी
न्यूनतम वेतन अधिनियम, 1948
छत्तीसगढ़, रायपुर