


**PROPOSED LABOUR SCHEDULE AL-9 PUT UP FOR RECOMMENDATION BY SoR
COMMITTEE IN ITS MEETING ON 29.11.2019**


Year 2019-20


**LABOUR SCHEDULE FOR LAST SPAN CABLING FOR SPAN LENGTH OF 50 MTR. IN 33 KV LINE
USING COVERED CONDUCTOR OF 70 & 99 SQ.MM. SIZE**


S. No.	Particulars	Unit	Qty.	Rate	Amount
1	Approach Clearence	Mtr	15	4.56	68.37
2	Pit digging	No.	1	364.66	364.66
3	Stay Pit digging	No.	2	303.88	607.76
4	Transportation of pole from road side to pole pit for a lead of 155 Mtrs.	No.	1	455.82	455.82
5	Shifting of materials (other than pole) to pole pits	No.	1	118.51	118.51
6	Cross arm fixing complete with top clamp	No.	1	121.55	121.55
7	Pole erection complete (including earthing)	No.	1	1215.52	1215.52
8	Concreting of stay and base pad for poles				
	(i) for 2 stay	Cft.	50	24.31	1215.50
9	Stay erection complete	No.	2	212.72	425.44
10	Insulator fixing at each location	No.	3	30.39	91.17
11	Anti climbing devices and danger board fixing	No.	1	75.97	75.97
12	Painting & numbering etc including steel support	No.	1	364.65	364.65
13	Stringing of line for all three Covered conductors of size 70 / 99 sq.mm. (3 Ph)	Mtr	155	13.67	2119.56
	TOTAL				7244.48


The schedule is to be prepared based on actual span length at site and requirement.



(Gopal Murty)
Addl.G.M., O/o GM (F&A)
CSPDCL Raipur



(S.K.Gajpal)
S.E., O/o CE(Project)
CSPDCL Raipur



(Chandrakala Gidwani)
S.E., O/o CE (S&P),
CSPDCL Raipur


(S.R.B. Khandelwal)
S.E., (Works) O/o ED (O&M)
CSPDCL Raipur


(A.K.Gauraha)
S.E., (Circle) CSPDCL Raipur


(Anish Kumar Lakhera)
S.E., (City Circle-I)
CSPDCL Raipur


(D.D.Choudhary)
E.E. (Civil- Maint.) Dn.
CSPDCL Raipur


(G.K.Gangwani)
E.E. O/o CE (EITC)
CSPDCL Raipur